

**ADDENDUM NO. 1**

**PROJECT: Township Road 133 Improvements**  
**OWNER: Canaan Township Trustees, Morrow County, Ohio**  
**BID OPENING: July 14, 2026, at 6:30 p.m.**

This Addendum forms a part of the Contract Documents and shall be acknowledged by all bidders. The following revisions and clarifications are hereby made to the bidding documents:

**1. Completion Date Correction**

Any reference in the project specifications to a completion date of October 31, 2024, is hereby revised to read:

**October 31, 2026**

The completion date stated on the Bid Proposal Form shall govern.

**2. Bid Quantity Revision – Berm Excavation**

Ref. No.	Item No.	Description	Original Quantity	Revised Quantity
1	203	Berm Excavation (6" deep × 24" wide)	537 CY	269 CY

The Bid Proposal Form is revised as follows:

All bidders shall base their bids on the revised quantity shown above.

**3. Contingency Amount Revision**

The Bid Proposal Form is revised as follows:

Description	Original Amount	Revised Amount
Contingencies	\$17,990	\$16,249

The revised contingency amount shall be used in preparing bids.

**4. Asphalt Density Testing Requirement**

Section 3.4 of the Asphalt Concrete Pavement Specifications is deleted in its entirety.

No density gauge testing shall be required for this project.

**5. Acknowledgment**

Bidders shall acknowledge receipt of this Addendum with their bid submission.

Except as specifically modified by this Addendum, all other requirements of the Contract Documents remain unchanged.

A revised Bid Proposal Form is attached to this Addendum. The attached form supersedes and replaces the original Bid Proposal Form included in the bidding documents. Bidders shall submit their bids using the revised form.

A revised Asphalt Concrete Pavement Specifications is attached to this Addendum with the revised completion date and removal of the 3.4 density gauge testing.

**CANAAN TOWNSHIP TRUSTEES  
MORROW COUNTY, OHIO**

**Date Issued: June 26, 2026**

---

**BIDDER MUST ACKNOWLEDGE THIS ADDENDUM BY SIGNING BELOW  
AND ATTACHING THE SIGNED ADDENDUM TO THE BID FORM(s):**

Company Name \_\_\_\_\_

Contact Person \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_

**THE CANAAN TOWNSHIP TRUSTEES OF MORROW COUNTY, OHIO  
REVISED BID PROPOSAL FORM, ISSUED WITH ADDENDUM No. 1**

**June 26, 2026**

The undersigned, having full knowledge of the site, plans and specifications for the following improvements, and the conditions of this proposal, hereby agrees to furnish all services, labor, materials and equipment necessary to complete the entire project, according to the plans, specifications and completion dates and to accept the unit prices specified below for each item as full compensation for the work in this proposal.

Date set for completion: October 31, 2026.

Contractor \_\_\_\_\_ By \_\_\_\_\_

The following list specifies the amount and type of materials to be used, as well as the application process to be used.

**Widening and resurfacing 1 mile TR 133 in Canaan Township**

Beginning at CR 28 then east to CR 130: 0.33 miles (1,745 feet) x 16' wide (existing pavement width) – Proposed width 16' wide.  
0.67 miles (3,535 feet) x 12' wide (existing pavement width) – Proposed width 16' wide.

**ITEM 441 HOT MIX**

Ref. No.	Item No.	Approx. Quantities	Units	Description	Unit Price Bid	Total Amount
1	203	269	CY	Berm Excavation (6" deep x 24" wide)		
2	304	269	Ton	Aggregate Base - 3"		
3	301	269	Ton	Asphalt Aggregate Base - 3"		
4	407	1,502	GAL	Tack Coat @ 0.08 gal/sy (2 applications)		
5	441	535	Ton	Asphalt Concrete, Intermediate course, type 1 – 1"		
6	441	535	Ton	Asphalt Concrete, Surface course, type 1 – 1"		
7	411/617	131	Ton	Shoulder aggregate (1.0' x 2")		
		1	LMP	Contingencies	xxxxxxxxx	\$16,249
				<b>TOTAL BID</b>		

1. Material for widening each side of TR 133 beginning at CR 28 then east 3,535 LF, by removing 6" of existing berm by 2 foot wide, installing 3" of 304 aggregate base, installing 3" asphalt aggregate base. Suspend and resume work at the bridge (40' long).

2. Material for paving full length of 1.00 mile by applying a 407 tack coat (0.08 gal/sy), installing 1" of 441 asphaltic scratch course full width (16'), applying 407 tack coat (0.08 gal/sy) installing 1" of 441 asphaltic surface course full width (16'), installing 411/617 aggregate shoulder material. Suspend and resume work at bridge (40' long).

The total amount of the bid, based on the approximate quantities given and the unit prices specified by the bidder amounts to the sum of \$ \_\_\_\_\_ dollars.

Date \_\_\_\_\_

**ASPHALT CONCRETE PAVEMENT SPECIFICATIONS**  
**Canaan Township Road 133 Improvements**  
**Addendum No. 1 Revision date 6.26.26**

**1.0 SPECIAL NOTES**

- 1.1 A preconstruction meeting will be required.
- 1.2 Completion date for the project is October 31, 2026.
- 1.3 Prevailing Wage Certification shall be submitted with all invoices.
- 1.4 A flagger shall be stationed at each point of closure (intersection) to direct traffic. Through traffic will be diverted around the closed area. Local traffic (residences and business) within the closure shall be provided access.

**2.0 SUPPLEMENT SPECIFICATIONS**

- 2.1 No bridge shall be resurfaced without prior authorization of the County Engineer.
- 2.2 Authorization may be given for reduced asphalt thickness on bridge decks and approaches thereto.
- 2.3 When bridge decks are resurfaced, the asphalt shall extend the full width and length of the deck.

**3.0 REFERENCE**

- 3.1 All references to specification numbers, unless otherwise noted on the plans or modified herein, shall refer to the respective section thereof in the Ohio Department of Transportation publication of Construction and Materials Specifications, latest edition.
- 3.2 The requirements of Section 400 of the Ohio Department of Transportation publication of Construction and Materials Specifications, latest edition, shall be used on this project, except as modified herein.
- 3.3 Section 401.20 of the Ohio Department of Transportation publication of Construction and Materials Specifications, latest edition. An asphalt binder price adjustment will not be applicable on this project.

**4.0 APPROVALS**

At or before the preconstruction meeting, the contractor shall submit the following for approval:

- 4.1 A printed schedule showing the interrelation and planned performance of all major items of work.
- 4.2 A list of key project personnel (Project Engineer/Manager, Project Superintendent, etc.) with office and mobile phone numbers to be used by the Township and staff.
- 4.3 A list of the paving equipment that will be used on this project (self-propelled paver, roller, distributor, etc.).
- 4.4 A list of proposed materials and suppliers.
- 4.5 The aggregate producer's current testing (including quality data) documentation for all stone property requirements of ODOT Item 703.05.
- 4.6 A list of subcontractors and key personnel representing each.
- 4.7 The proposed Job Mix Formulas (submitting in ODOT format).
- 4.8 The Canaan Township Trustees office will respond to the items submitted within two (2) weeks. If an item is not approved, the contractor will have two (2) weeks from the time of notification to resubmit; the Engineers office will respond within two (2) weeks of resubmission. No mix shall be produced until approval is granted.