

Addendum #1
Date: July 2, 2024
Project: Canaan Township Road 60 Improvements
Phase 4
OPWC Issue 1

- A. This Addendum shall be considered part of the bid documents for the above-mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original bid documents, this Addendum shall govern and take precedence. BIDDERS MUST SIGN THE ADDENUM AND SUBMIT IT WITH THEIR BIDS.

- B. Proposers are hereby notified that they shall make any necessary adjustments in their estimates as a result of the Addendum. It will be construed that each bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

Except as described below, the original bid document remains unchanged. The bid documents are modified and/or clarified, as follows:

Reference No. 3 updated

Item No. 304

Approximate Quantities: 196 ton

Aggregate Base, 3"

Reference No. 4 updated

Item No. 301

Approximate Quantities: 196 ton

Asphalt Aggregate Base, 3"

BIDDER MUST ACKNOWLEDGE THIS ADDENDUM BY SIGNING BELOW AND ATTACHING THE SIGNED ADDENDUM TO THE BID FORM(S):

Company Name _____

Contact Person _____

Signature _____

Date _____

THE CANAAN TOWNSHIP TRUSTEES OF MORROW COUNTY, OHIO

The undersigned, having full knowledge of the site, plans and specifications for the following improvements, and the conditions of this proposal, hereby agrees to furnish all services, labor, materials, and equipment necessary to complete the entire project, according to the plans, specifications and completion dates and to accept the unit prices specified below for each item as full compensation for the work in this proposal.

Date set for completion: October 31, 2024

Contractor _____ By _____

The following list specifies the amount and type of materials to be used, as well as the application process to be used.

Resurfacing and widening 1 mile of T.R. 60 in Canaan Township. Existing width 14 ft. to be widened to 16 ft. Beginning at TR 67 then north to CR 61. Paving to continue through the intersection of TR 60 and CR 61. Also includes the installation of new tile at the intersection of TR 65 and TR 60.

ITEM 441 HOT MIX

Ref. No.	Item No.	Approx. Quantities	Units	Description	Unit Price Bid	Total Amount
1	202	30	LF	Remove Existing Conduit		
2	203	196	CY	Berm Excavation (6" deep x 12" wide)		
3	304	196	Ton	Aggregate Base, 3"		
4	301	196	Ton	Asphalt Aggregate Base, 3"		
5	407	1,502	GAL	Tack Coat @ 0.08 gal/sy (2 applications)		
6	441	535	Ton	Asphalt concrete, intermediate course, type 1 - 1"		
7	441	535	Ton	Asphalt concrete, surface course, type 1 - 1"		
8	441/617	131	Ton	Shoulder aggregate (1.0' x 2")		
9	661	30	LF	Install N-12 Conduit, 10"		
		1	LMP	Contingencies		\$ 13,592.00
				TOTAL BID		

All aggregate to be limestone. This work shall consist of material for installing 1" of 441 asphaltic intermediate course full width (16'), installing 1" of 441 asphaltic surface course full width (16'), installing 441/617 aggregate shoulder material and pave intersection plus the approaches at TR/CR 61.

The total amount of the bid, based on the approximate quantities given and the unit prices specified by the bidder amounts to the sum of \$ _____ dollars.

Date _____